



Fred L. Krapff
Utility Contractor
James "Jim" L. King

Mr. Thomas Helvick, PE.
Garver
750 SW 24th St. Suite 200
Moore, OK 73160

January 23, 2026

RE: Clinton Sewer Improvements

Mr. Helvick, We are pricing the installation of junction boxes to reroute the 24" Storm piping.

The following items will need to be added by an amendment to the quantities:

Item 22 – Removal of Concrete Pavement, add 53 SY @ \$10.00 per SY	\$530.00
Item 23 – Concrete Pavement Placement, add 53 SY @ \$200.00 per SY	\$10,600.00
Item 24 – Standard Bedding Material or Backfill, add 115 CY @ \$60.00 per CY	\$6,900.00
Item 26 – Combined Curb & Gutter (6" Barrier), add 36 LF @ \$125.00 per LF	\$4,500.00
Item 27 – Removal of Curb and Gutter, add 36 LF @ \$10.00 Per LF	\$360.00

The following items will need to be added by change Order:

Item CO 7.1 – Additional Traffic Control, add 1 LS @ \$1,952.00 per LS	\$1,952.00
Item CO 7.2 – 4' x 10' Storm Junction box, add 2 EA @ \$9,083.00 per EA	\$18,166.00
Item CO 7.3 – RCP Storm Pipe (24"), add 24 LF @ \$913.00 per LF	\$21,912.00

Total Additions by Amendment to Quantities	\$22,890.00
Total Additions by Change Order to Quantities	\$42,030.00
<u>Net Addition to Contract</u>	<u>\$64,920.00</u>

JUSTIFICATION – Due to the existing 24" RCP storm sewer being in the same alignment as proposed manhole 15, the storm system will need to be rerouted. This will involve additional traffic control, excavation, materials and pavement removal and replacement. We will also need additional time to complete this work. Therefore, we are requesting 60 days be added to the contract.

Respectfully,

Wade Vakulick,
Project Manager,
Krapff Reynolds Const. Co.





