

CITY OF CLINTON

MEMO

DATE: November 14, 2008

FROM: Arnold Adams, PW Director

TO: Grayson Bottom

RE: Gary Blvd Panels

I am recommending that the City of Clinton replace more panels on Gary Blvd. After the recent completion of the panels replaced by Wittwer Construction, Myself and Monty Proffitt, Street Supervisor, would like to recommend replacing an additional 3,300 sq.ft.of concrete.

I have spoken with David Burns with Wittwer Construction; he said they would honor their original contract of \$15.00 sq ft if we act quickly, before they move out all their equipment and manpower.

The following is a breakdown of the cost to tear out and replace the panels with 3,500 lb concrete:

Safety Barricades – \$5000.00

Pins & Baskets – \$500.00

Sand to Level – \$300.00

Labor to Place Concrete – 3300 @ \$5.00 sq ft = \$16,500.00

3500 # Concrete – 371 yds @ \$93.00 per yd = \$34,503.00

For a total cost of \$56,803.00

This figure does not include our labor & equipment to tear out and remove concrete.

Note: If we do this ourselves, for which we do not have the right equipment, I figure it would take us 4 -5 Weeks to complete. Wittwer Construction assures me they can complete the job in 1 – 2 weeks maximum.

Sincerely,

Arnold Adams