



# FISCHER BROS. LLC

*Waterslide Restoration*

City of Clinton  
415 Gary Blvd.  
Clinton, OK 73601

November 22, 2010

Fischer Bros. LLC  
50669 East St.  
Osseo, WI 54758

Proposal #2026

**ATTN: Kris Wermey**

Kris,

Fischer Bros. LLC is pleased to submit a proposal for the complete restoration of one 210' Miracle open flume waterslide located in Clinton, Oklahoma.

## **Scope of work**

Fischer Bros. will supply all necessary labor, supervision, and materials for the completion of the following items:

### **Restoration of waterslide exterior**

- Previously applied coating will be removed as necessary to ensure adequate adhesion of new coatings.
- Coatings will be airless spray applied for a smooth finish.
- Any color can be selected for restoration.
- Newly recoated surface repels dust and grime buildup, unlike existing gelcoat.
- Gloss and color retention of newly recoated surface is 2-3 times greater than original gelcoat surface.
- All flange hardware will be removed and replaced with new stainless hardware.

## **Restoration of waterslide interior**

- Entire interior surface will be aggressively sanded using high speed orbital sander w/ 50-60 grit to remove all of the previously applied marine coating.
- Entire interior surface will be lightly sanded to remove high spots with Pneumatic DA w/ 60-80 grit.
- Seams will be cut out with a 3/16" diamond cutter to a depth of 3/8", removing old sealant and leaving an ideal surface for new sealant to gain adhesion, as well as ensuring that new sealant will penetrate deeply into seam.
- All surface imperfections (chips, deep scratches, spider cracks, gouges, weak areas) will be repaired using appropriate fillers such as short strand moisture proof fiberglass filler and/or clear resin gel. Any previous repairs will be completely reworked to ensure a safe, problem free slide.
- Fiberglass will be reinforced as necessary at the contractors discretion.
- TNEMEC Series N69 will be airless spray applied as a basecoat.
- TNEMEC Series 73 or Series 701 will be airless spray applied for a nearly flawless interior finish.
- Entire surface will be lightly wet sanded by hand using 400-600 grit paper to remove any small nicks or imperfections.
- All seams will be recaulked using Sikaflex 291.
- Any hardware (handles, grates, etc) that had been previously removed will be replaced using new stainless hardware when necessary.

## **New steel supports**

- Several of the steel slide supports are severely corroded and need to be replaced. These supports will be duplicated and replaced. New supports will be constructed out of stainless steel to ensure that they will not corrode in the future.
- New supports will be painted to match the surrounding steel.

## **Pricing**

**Exterior restoration/hardware replacement    \$19,400**

**Interior restoration** **\$14,700**

**New supports** **\$3,200**

**Total** **\$34,130**

**Discounted total if retained to complete all work offered** **\$31,250**

### **Completion time/Access**

The time required to finish this project is approximately 14-16 days. Uninhibited access to the facility is necessary, as our crews work seven days a week during the busy spring and fall seasons. Electrical and clean water supplies must be made available for us to complete our work.

### **Liability Insurance**

Fischer Bros. LLC and any subcontractors that may be used will comply with all State, County, City, EPA, and OSHA regulations that apply to this type of contract service and will furnish a Certificate of Commercial Liability Insurance evidencing sufficient coverage and naming City of Clinton as Additionally Insured if necessary.

### **Site Demobilization**

All debris and garbage created by above mentioned work will be disposed of properly upon project completion. Representatives of Fischer Bros. or any subcontractors will not leave the project unexpectedly, but will “walk the work” with a representative of the City before departure to ensure complete satisfaction.

Fischer Bros. will keep the site clean and tidy at all times, and materials will be stored in an orderly fashion during the course of the project. We are aware of, and will respect the local public and its vested interest in this facility.

### **Terms of payment**

40% down

Remainder upon completion (within 15 days of completion of project and receipt of final invoice)

## Price Validity

This proposal is valid until July 1, 2011. After that date changes may or may not be made.

Fischer Bros. LLC is excited about restoring this feature within your facility, and we are looking forward to a long and mutually beneficial relationship with the City of Clinton.

Approved by \_\_\_\_\_ Date \_\_\_\_\_

Print name and Title \_\_\_\_\_

\_\_\_\_\_ Date \_\_\_\_\_

Andrew J. Fischer

Managing Member