

# COBB ENGINEERING

June  
~~May~~ 6, 2012

Honorable Mayor and City Council  
City of Clinton  
P.O. Box 1177  
Clinton, Oklahoma 73601

RE: Recommendation of Contract Award  
Reconstruct Hangar Aprons, AIP 3-40-0021-011-2012  
Clinton Regional Airport

Honorable Mayor and City Council:



Construction bids for referenced project were received on June 5, 2012, and the tabulation of those bids is enclosed.

The low bidder was Circle S Paving Company, Inc., and we recommend the contract be awarded to them in the amount of \$353,881.30 for the Base Bid. As their bid was below our estimate, we see no reason to award either of the alternate deduct bids.

We greatly appreciate the opportunity of serving you on this important development for your airport.

Respectfully submitted,

COBB ENGINEERING COMPANY

Toby J. Baker, P.E.  
Engineering Manager  
Airport Planning and Design

Enclosure (1)

cc: Mike Nguyen, FAA

WWW.COBBENGR.COM  
4516 NW 36TH STREET / OKLAHOMA CITY, OK 73122-2426 / PHONE: 405.415.9400 / FAX: 405.415.9410

N:\OKC\Airport\Clinton Regional\2012\Reconstruct Hangar Aprons\Correspondence\Letter to Mayor and Council - Recommendation of Award.doc

## TABULATION OF BIDS

Reconstruct Hangar Aprons

5:30 PM

AIP Project 3-40-0021-011-2012

6/5/2012

Clinton Regional Airport

City Council Chambers

Clinton, OK

Item	Description	Quantity		Cornell Construction		Circle S Paving		Engineer's Estimate	
				Unit Price \$	Amount \$	Unit Price \$	Amount \$	Unit Price \$	Amount \$
<b>Base Bid</b>									
1	Mobilization	1	LS	25,000.00	25,000.00	3,000.00	3,000.00	8,000.00	8,000.00
2	Low-Profile Flag and Flasher Barricades	1	LS	1,500.00	1,500.00	1,200.00	1,200.00	2,500.00	2,500.00
3	Construction Staking	1	LS	4,993.83	4,993.83	4,000.00	4,000.00	5,000.00	5,000.00
4	Temporary Erosion Control	1	LS	3,444.48	3,444.48	3,500.00	3,500.00	4,000.00	4,000.00
5	Asphalt Pavement Removal	8,600	SY	4.03	34,658.00	2.00	17,200.00	3.00	25,800.00
6	Remove and Replace Topsoil	1	LS	7,217.29	7,217.29	2,500.00	2,500.00	7,000.00	7,000.00
7	Unclassified Excavation	1	LS	24,291.30	24,291.30	2,000.00	2,000.00	10,000.00	10,000.00
8	Install 18" RCP	271	LF	78.50	21,273.50	44.90	12,167.90	45.00	12,195.00
9	Install Single Grate Inlet	2	EA	1,594.14	3,188.28	1,200.00	2,400.00	2,500.00	5,000.00
10	Triaxial Geogrid	9,100	SY	5.33	48,503.00	5.00	45,500.00	4.70	42,770.00
11	6" Crushed Aggregate	9,100	SY	9.13	83,083.00	10.00	91,000.00	11.00	100,100.00
12	Prime Coat	4,548	Gal	3.42	15,554.16	3.80	17,282.40	3.25	14,781.00
13	3" P-403 Asphalt	1,550	TON	111.75	173,212.50	90.00	139,500.00	90.00	139,500.00
14	Reflective Marking	550	SF	1.26	693.00	2.50	1,375.00	2.50	1,375.00
15	Solid Slab Sodding & Watering Until Established	4,020	SY	6.50	26,130.00	2.80	11,256.00	3.00	12,060.00
16	Third Party Insurance	1	LS	-	0.00	-	0.00	-	0.00
<b>TOTAL BASE BID</b>				<b>\$472,742.34</b>		<b>\$353,881.30</b>		<b>\$390,081.00</b>	

<b>Alternate No. 1</b>									
17	OMIT BID ITEM 8 (DEDUCT)	1	LS	(21,273.50)	-21,273.50	(12,167.90)	-12,167.90	(12,195.00)	-12,195.00
18	18" CGMP	271	LF	67.50	18,292.50	42.50	11,517.50	25.00	6,775.00
<b>TOTAL ALTERNATE NO. 1</b>				<b>-\$2,981.00</b>		<b>-\$650.40</b>		<b>-\$5,420.00</b>	

<b>Alternate No. 2</b>									
19	OMIT BID ITEM 8 (DEDUCT)	1	LS	(21,273.50)	-21,273.50	(12,167.90)	-12,167.90	(12,195.00)	-12,195.00
20	18" HDPE	271	LF	65.25	17,682.75	39.50	10,704.50	35.00	9,485.00
<b>TOTAL ALTERNATE NO. 2</b>				<b>-\$3,590.75</b>		<b>-\$1,463.40</b>		<b>-\$2,710.00</b>	