



Agenda Commentary

Item Title/ Subject: Accept and approve bids for Waste Water Clarifier rehab

Staff Source: City Manager, Steve Hewitt

Date: August 17, 2012

History/Background Information:

DEQ provided the City of Clinton a direct mandate to have our Waste Water Treatment Facility Clarifier Tanks Rehab by the end of 2012.

Item/Subject Summary:

This is a budgeted item and requirement. (see bid notice and scope).

Price/Cost: TBD

Recommendation:

TBD

BID NOTICE

Notice is hereby given that the Clinton Public Works Authority of Clinton, OK is seeking sealed bids for furnishing all necessary materials, equipment, machinery, superintendence, labor, insurance, and other required provisions for:

REHABILITATION OF CLARIFIER TANKS AT CLINTON WASTEWATER TREATMENT PLANT IN CLINTON, OKLAHOMA

Sealed bids shall be submitted to the Office of the City Clerk, 415 Gary Boulevard, Clinton, Oklahoma, 73601, no later than Tuesday, August 21, 2012 at 5:30 P.M. in a sealed envelope marked "**REHAB OF CLARIFIER TANKS**". Bids submitted more than 96 hours before the time of the bid opening will be returned unopened to the bidder submitting the same.

Properly submitted bids will be opened for consideration at a regular meeting of the Clinton Public Works Authority of Clinton, Oklahoma at 5:30 P.M. Tuesday, August 21, 2012.

All bids shall be firm for 30 days. Bids shall be submitted based upon specifications and contract documents, which may be obtained from the Office of the City Clerk, 415 Gary Boulevard, Clinton, OK. 73601. (580-323-0265)

The Clinton Public Works Authority reserves the right to reject any and all bids and to accept the bid which best meets the needs of the Clinton Public Works Authority.

All bidders are invited to attend the bid opening.

Steve Hewitt
City Manager
City of Clinton, OK.

Clarifier Rehab Clinton, OK. – Scope of Work

Scope of Work:

Successful bidder to provide all Material and Labor in order to sandblast and paint clarifier tanks #1 and #2, at the Clinton, Oklahoma Waste Water Treatment Plant. Bidder is encouraged to review the job site prior to bidding.

General rehab scope is to remove all mechanical parts, sandblast and paint and to reinstall all mechanical parts. This includes the following.

- 1) Remove and install electrical wiring on bridge to drive assembly.
- 2) Remove, sandblast & paint, and reinstall bridge.
- 3) Remove, sandblast & paint, and reinstall center support, stilling well, rake arms. Disassemble all bolt connections to facilitate sandblast and paint of internal surfaces.
- 4) Remove, and install, align and level drive.
- 5) Remove, sandblast & paint, and reinstall baffle plates, and weir troughs.
- 6) Remove, install and level weirs, to facilitate sandblast and paint of troughs.
- 7) Repair to entrance and exit of beach.
- 8) Replace existing skimmer wiper with OEM equipment and level to OEM specifications.
Straightening of supporting structural steel will be required to return the skimmer to like new condition. All field welding to be performed by AWS certified welders and to AWS procedures. Skimmer must be realigned to meet the beach.

All work to be performed in a timely and professional manner.