

CHANGE ORDER NO. 3
Flow Meter Additions at Clinton Lake WTP

TO: Lonehickory Cattle LLC ("Contractor")

DATE: February 1, 2017

Upon Contractor acceptance and the City of Clinton ("City") approval, the work and Contract Documents for City of Clinton Project entitled Golf Course Raw Waterline shall be adjusted to include the following:

ADDITIONS:

The City has requested piping and flow meter additions at their Clinton Lake WTP. These additions would provide for a new 8" flow meter/valve/vault near the existing meter vault, and another 8" flow meter inside the plant building. This would allow for precise flow measurement and chemical dosing over a wider range of plant flow rates compared to existing flow measurement equipment. This work will be paid on a lump sum basis commensurate with the percent of work completed.

DEDUCTIONS:

A correction to Change Order #2 is included as part of this Change Order as a result of an addition error. Change Order #2 reflected a Contract Total of \$892,510.00 where it should have been \$882,510.00. The \$10,000 error is corrected below.

Adjustments to Contract Price & Time

Item Description	Contract Dollars	Calendar Days
Contract Totals (to date)	\$892,510.00	120
Correction to Change Order #2	-\$10,000.00	0
Adjustments this Change Order No. 3	\$77,638.72	120
Contract Totals to Date – Including Change Order No. 3	\$960,148.72	240

Contract Time Expires on: **May 3, 2017.**

Acceptance of this Contract Change Order by the Contractor is a complete waiver and release by it, its subcontractors, and its suppliers of all direct, indirect, consequential and impact-related costs resulting from or related to this Change Order, and its effect, if any, on unchanged Work, including, but not limited to, delays, impacts and disruption as well as extended or increased jobsite and home office overhead costs that may be experienced or incurred as a result of performance of this Change Order.

This document will become a supplement to the Agreement and all of its provisions will apply hereto.

ACCEPTED FOR CONTRACTOR

By Wes Collins

Print Name Wes Collins

owner

2-3-17

APPROVED FOR CITY OF CLINTON

By _____

Print Name _____

The Change Order # 3 that is the plant work at Clinton Lake.

We plan to install two 8" meters, and valves with telemetry capabilities.

The meter and valve inside the plant consist of approximately three days of professional welding and fabrication of new piping using the equipment of a Genie Forklift.

The work outside is a new meter and valve that can be controlled inside with telemetry capabilities in 18 x 8 interconnect and a new meter vault. The equipment being used for this is a CAT 318 Excavator and a CAT skid steer.

A 24" Tee and Fire Hydrant for water testing purposes.

Also, we plan to enclose the building for the Chemical Feed Building and insulate it as well.