

Floor-Tech Janitorial, LLC# 202924253

# Proposal

P.O. Box 937  
Bethany, OK 73008

Date	Estimate #
7/2/2018	301

Name / Address
Teel Consulting 3601 W. Model Clinton, OK. 73601

Project

Description	Qty	Cost	Total
<p>Customer to pressure wash floor before work begins. Labor and materials to scrub using Auto Scrubbers, thoroughly rinsed and two coats of waterborne epoxy applied . After epoxy two coats of epoxy is applied and has cured for at least 12 hours, two coats of Floor-Tech's Conceal waterborne clear coat will be applied.</p> <p>Paint chips and aggregate will be added improved footing.</p> <p>This is a two component epoxy system some what more labor intensive however is more durable.</p> <p style="text-align: right;">Complete Janitorial Line Hardwood Sand &amp; Finish Strip &amp; Finish</p> <p><b>FLOOR-TECH JANITORIAL</b> Sales and Service</p> <p style="text-align: center;">P. O. Box 937 • Bethany, OK 73008</p> <p><b>BOB HINER</b> Owner rhiner@cox.net</p> <p style="text-align: right;">405-833-6693 Cell 405-603-2647 Fax 405-603-2583 Office</p>	13,000	1.90269	24,735.00
			0.00

<b>Subtotal</b>	\$24,735.00
<b>Sales Tax (8.375%)</b>	\$0.00
<b>Total</b>	\$24,735.00

**PROPOSAL**

WILLIS PAINTING LLC  
1515 E. Main #104  
Weatherford, OK 73096  
Home: (580)772-1998  
Cell (580) 819-0145  
Fax (580)772-0067

Date: 6/1/18

Proposal Submitted To:

Teel Consulting, Inc.  
Attn: Lonnie Teel  
406 College Ave.  
Harper, KS 67058  
Teelconsultinginc.com  
(405)368-0578

RE: Clinton RO Plant Floor

We hereby propose to perform all the labor and provide all the material necessary for the completion of:

1. Surface Prep., use ICRI CSP 2-3;
2. Coat 1: IP3569A54 – General Polymers 3569 (reduced 25%)
3. Coat 2: IP3569A54 – General Polymers 3569
4. Coat 3: B65A00060 – ArmorSeal Rexthane I Floor Coating.

All material is guaranteed to be as specified and the above work to be performed in accordance with drawings and specifications submitted for above work and completed in a substantial workmanlike manner for the sum of Twenty five thousand dollars (\$25,000.00)

Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders and will become an extra charge over and above the estimate.

Respectfully submitted: \_\_\_\_\_  
Dyrek Willis

**ACCEPTANCE OF PROPOSAL**

The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Accepted: \_\_\_\_\_ Signature: \_\_\_\_\_  
Date: \_\_\_\_\_ Signature: \_\_\_\_\_



2/19/2018

Wynn Construction

Clinton, OK WTP

Please find our proposal to apply an epoxy/urethane floor system at Rooms 105 & 106.

Labor and Materials (3 coat option) .....	\$33,860.00
2 coat option - Dedect .....	(\$7,500.00)

Scope of Work

Surface prep to ICRI CSP3  
Apply 2 coat Tnemec Series 237P Epoxy  
Apply 1 coat Tnemec Series 290 Urethane  
Equipment pads are not included.

Please feel free to contact me with any questions.

Thanks,

Randy Penrod  
RP Coatings, Inc  
618-521-9528  
[randy@rpcoatings.com](mailto:randy@rpcoatings.com)