

**Matherly Mechanical
Contractors, LLC**



P.O. Box 30889 1520 OCAMA Boulevard
Midwest City, Oklahoma 73140
Phone (405) 737-3488 Fax (405) 737-9211

**PROPOSAL
September 22, 2023**

Clinton Hospital

Attn: Mike Thomas

Mike,

Below is our scope and price for Install of 5 Humidifiers and 5 Dispersion tubes with associated piping (Steam, cold water, and condensate drain). Demo and replace damaged Insulation on the roof.

Inclusions:

- 1. Normal working hours M-F**
- 2. Install 5 Neptronic humidifiers and 5 Dispersion tubes.**
- 3. Install steam piping from humidifiers to the dispersion tubes.**
- 4. Demo heating coils in the duct work**
- 5. Install cold water piping to 5 humidifiers.**
- 6. Install and route condensate drain piping from humidifiers to nearest drain.**
- 7. Electrical Power to the Neptronic Humidifiers, 50-amp breaker, panel, disconnects, and thermostats.**
- 8. Insulate Domestic cold water, Steam, and Condensate drains associated with humidifiers.**

Exclusions:

- 1. Overtime/Shift pay**
- 2. Engineering**
- 3. Tab**
- 4. DDC and or any Controls**
- 5. Painting and or Sheetrock work**
- 6. Fire alarm system and smoke detection system**
- 7. Chemicals in chilled water i.e., glycol**
- 8. Ceiling removal and Installation**

BASE BID AMOUNT
\$99,100.00

Alternate Add

Alternate add for the 2" fiberglass duct board and finished with glass Cloth and mastic to match existing duct insulation on the roof, includes demolition of existing Insulation on the roof.

- 25''x 43''x (32')
- 104''x 16''x (36')
- 30''x 32'' x (16')
- 46''x 16'' x (8')

Alt. Add: \$43,960.00

Proposal is Good for 45 Days

Call with questions

Sincerely,

**Matherly Mechanical Contractors, LLC.
Joe Shiff / Estimator**